BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT45020

MODIFIED SCHEDULE-B

No.EE/BTP/BBMP/E-PMT/07/2020-21, Date: 19-09-2020

Name of the Work : Package-1, includes 5 works of Rs.300.00 lakhs

Sl. No.	Modified Quantity.	Description	Unit	Approved Tender Rates of Chidananda murthy R	
				In Figures	In Words
1	1429.85	Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	256.07	Rupees Two Hundred Fifty Six and Seven Paise Only
2	9532.35	Removing and refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	116.87	Rupees One Hundred Sixteen and Eighty Seven Paise Only
3	2383.09	Providing granite slabs of selected quality roughly dressed havinf a size of 7.5 cms thick and fixed in cement mortar (1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	779.10	Rupees Seven Hundred Seventy Nine and Ten Paise Only
4	635.49	Providing and laying **Plain cement concrete of mix 1:3:6 with with OPC cement @ 220kgs, with crushed 40mm** and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @ 0.56cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days etc complete as per specifications and directions of engineer in charge of the work	cum	5693.00	Rupees Five Thousand Six Hundred Ninety Three Only
5	5648.80	Providing and constructing load bearing wall with solid concrete blocks of size 400x150x200 mm having block density not lessthan 1800 kg/m3 and having a minimum average compressive strength 4.00 N/mm2 confirming to IS 2185 (Part) : 2005 and constructed with CM 1:4 , as per IS 2572:2005 including cost of all materials, labour charegs, scaffolding, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	1028.41	Rupees One Thousand Twenty Eight and Forty One Paise Only
6	732.73	Providing and laying in position **plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size** graded granite metal coarse aggregates @ 0.69 cum and fine aggregtes @ 0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, for coping. Including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work	cum	5879.98	Rupees Five Thousand Eight Hundred Seventy Nine and Ninety Eight Paise Only
7	4828.50	Providing granite slabs of selected quality roughly dressed havinf a size of 10 cms thick and fixed in cement mortar (1:6) including fixing curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	1015.06	Rupees One Thousand Fifteen and Six Paise Only

Sl. No.	Modified Quantity.	Description	Unit	Approved Tender Rates of Chidananda murthy R	
				In Figures	In Words
8	27040.00	Providing chamfering edges to stone slab 2.5 cms. wide as per specifications. (only chamfered length shall be recorded) etc complete as per specifications and directions of engineer in charge of the work	m	64.49	Rupees Sixty Four and Forty Nine Paise Only
E1	1134.00	Providing precast slab of 100mm thick including cost of all materials, labour, curing, transportation, loading unloading, etc.,complete as per the direction of engineer in charge - (Data rate Approved). As per PWD SR 2018-19	Sqm	2453.62	Rupees Two Thousand Four Hundred Fifty Three and Sixty One Paise Only
E2	2800.00	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete Page No. 27 / Item No. 5.30 PWD SR 2018-19	No	454.06	Rupees Four Hundred Fifty Four and Six Paise Only
E3	504.00	KSRB 15-19.1 : Providing and applying ready mix priming coat over concrete / masonry / asbestos cement sheet / plastered surfaces including preparing the surface after thoroughly cleaning of oil, grease, dirt and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications. Page No. 124 / Item No. Item No. 15.80, PWD SR 2018-19	Sqm	41.18	Rupees Forty One and Seventeen Paise Only
E4	504.00	KSRB 15-19.2 : Providing and applying spray painting in two coats (excluding priming coat) over concrete / masonry / asbestos cement sheet / plastered surfaces with flat wall paint of approved brand to give even shade after cleaning the surface of all dirt, dust and other foreign matter, and sand papering including cost of materials, labour, complete as per specifications.Page No. 124 / Item No. Item No. 15.81, PWD SR 2018-19	Sqm	94.60	Rupees Ninety Four and Fifty Nine Paise Only
E5	144.00	Providing and instalation at site of works P.V.C.Pipes including cost of pipes and specials and incluidng lowring into trenches, laying true to line, level and perfect linking at joints, leak proof including jointing encasing the pipe alround to a depth Not less than 15cm with grave or selected earth avalabile from the execavation Etc., Page No.61 item No. 10.01.2 b PRED SR 2019-20.	Rmtr	217.33	Rupees Two Hundred Seventeen and Thirty Two Paise Only

Signature of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92